

15-169-00066-00-00

CP-3

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

DEC 27 1962
12-27-1962

Operator's Full Name Duck Supply Co.
Complete Address: 5830 Birchwood Great Bend, Ks
Lease Name Rehder Well No. 1
Location SE 1/4 NW 1/4 SE SW Sec. 19 Twp. 15 Rge. 2 (E) (W)
County Saline ^{AWB KCC} Total Depth 3391'
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated: _____
Plugging Contractor: Knight Casing Co.
Address: Box 304 Chase, Ks. License No. 436
Operation Completed: Hour 2pm Day 20 Month 12 Year 1962

The Above well was plugged as follows:

filled hole with sand from TD 3391' back to
3365'. Ran 5' sap cement with dumphailer
shot off & pulled 5 1/2" casing. Filled hole with
mud from 3305' back to 265'. Set 10' rock
bedg. & 20' sap cement. Filled hole with mud
from 195' back to 30'. Set 5' rock & 8' sap
cement back to zero. 8 1/2" surface pipe
3' below gr. level.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12-27-62
INV. NO. 6324-w

Signed: [Signature]
Well Plugging Supervisor