

STATE CORPORATION COMMISSION

15-169-00811-00-00

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Midwest Supply Company

Complete Address 343 Marmaton Road, El Dorado, Kansas 67042

Lease Name Richter Well No. 3

Location SW NW SW Sec. 19 Twp. 15 Rge. 3 (E) (W) X

County Saline Total Depth 3410'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Buckeye Corporation

Address P.O. Box 1020, El Dorado, Kansas License No. 687

Operation Completed: Hour 2 PM Day 4 Month June Year 1974

The above well was plugged as follows:

Pipe collapsed and parted at 1900'. Pushed plug to 1900' and dumped
3 sacks cement on plug. Filled hole with mud to 215'. Set rock bridge
from 215' to 200' and cemented hole with 25 sacks cement.

Filled hole with mud to 40'. Set rock bridge from 40' to 30' and cemented
hole to base of cellar with 10 sacks cement.

1900' of 4 1/2" casing recovered.

I hereby certify that the above well was plugged as herein stated.

Signed: *Arthur J. Turner*
Well Plugging Supervisor

INVOICE:

DATE 6/11/74

INV. NO. 9268-W