

15-169-19115-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION CW/2-SW-SE

SEC. 13 TWP. 15 RGE. 3W

Dry Hole _____ Abandoned Oil Well *** Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease John W. Muir. Box 33

Operator Louis H. Mai Address Russell, Kansas.

Field _____ County Russell, Saline

Total Depth 3266' Feet.

(Describe briefly the manner in which the well was plugged)

Plugging Contractor.- Barnes & Sons Pipe Pulling Co.

Plugging Contractor's License No. 9

Address.- Russell, Kansas.

Surface pipe - 13 3/8" @ 120' c.v.c. 150 sx. 9 5/8" @ 275' c.v.c. 250 sx.

7" @ 3254' Cem. 75 sx. Sand back to 3240' @ 6 sx. cem. with dump bailer.

Ripped 7" off @ 2600' & pulled same. Mud hole to 270' from top, set rock

bridge and 20 sx. cem. with dump bailer. Mud to 35' from top, set

rock bridge and 10 sx. cem. to base of cellar.

PLUGGING
FILE SEC. 13 T. 15 R. 3W
BOOK PAGE 122 L. 24

RECEIVED
STATE CORPORATION COMMISSION
12-05-50 DFC
District Conservation Agent
CONSERVATION DIVISION
Wichita, Kansas
12-4-56