

15-169-19113-00-00

Form CP-3  
Rev. 6-26-62

<sup>10</sup>  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 27 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Tom C. Brown

Complete Address: Box 387, Lindsborg, Kansas

Lease Name Muir Well No. 2

Location C NE NE Sec. 13 Twp. 15 Rge. 3 (E) (W) X

County Saline Total Depth 3256'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 4 PM Day 22 Month April Year 1964

The Above well was plugged as follows:

Hole filled with sand to 3240' and cemented with 3 sacks.

Hole filled with mud to 210'. Rock bridge set from 210' to 200' and

cemented with 20 sacks. Hole filled with mud to 40'. Rock bridge set

from 40' to 30' and hole cemented to base of cellar with 10 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 4/28/64

INV. NO. 9037-4

Signed: [Signature]  
Well Plugging Supervisor