

15-169-00836-00-02

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

NOV 6 1963
11-4-63
RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

Operator's Full Name Frank J. Black

Complete Address: P.O. Box 150, McPherson, Kansas

Lease Name Alan Johnson Well No. 1

Location SE SW NW Sec. 34 Twp. 15 Rge. 3 (E) (W) X

County Saline Total Depth 3367'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 11 AM Day 29 Month October Year 1963

The Above well was plugged as follows:

4 1/2" plug pushed to 3110'. Hole filled with sand to 3100' and cemented
with 3 sacks. Hole filled with mud to 270'. Rock bridge set from 270'
to 260' and hole cemented with 20 sacks. Hole filled with mud to 40'.
Rock bridge set from 40' to 30' and hole cemented to base of cellar
with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 11/4/63

INV. NO. 8014-W