

KANSAS

Form CP-3  
Rev. 6-4-68

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202API Number 15 -169-20,099-00-00 (of this well)

Operator's Full Name Ratten Oil Company  
Complete Address Suite 200, 5660 Syracuse Circle, Englewood, Colorado  
Lease Name Brown "C" Well No. 1  
Location C NE NE Sec. 32 Twp. 15 Rge. 3 (E)    (W) X  
County Saline Total Depth 589'  
Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A     
Other well as hereafter indicated Lost hole - Lost Circulation Zone  
Plugging Contractor Big Springs Drilling, Inc and Allied Cementing Co.  
Address Box 8287 Munger Station, Wichita, Kansas License No.     
Operation Completed: Hour 11:30 AM Day 13 Month March Year 1980

The above well was plugged as follows: 8 5/8" - 300' - 200' in bottom and 725 sacks into collar  
Above lost circulation zone.

Ran drill pipe to 589' and tried to fill hole; unable to do so.  
Pulled drill pipe to 310' and pumped 100 sacks 50-50% mix w/4% gel  
and 4% calcium chloride at 310'. Let set 2 hrs. Top 260'. Pumped 75  
sacks cement through drill pipe at 240'. Lined down drill pipe  
and pumped 25 sacks into 8 5/8" - Filled to collar. Pumped 15  
sacks cement into rat hole.

(Lost circulation zone at 255')

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 3-18-80  
REV. NO. 1742W