


15-169-19098-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Saline County, Sec. 30 Twp. 15 Rge. 3 W (E) (W)  
Location as "NE/CNW/SE" or footage from lines C S/2 SE NW  
Lease Owner Arvel Smith  
Lease Name Larson Well No. 3  
Office Address Rt. 1 Towarda, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 7-24 19 51  
Application for plugging filed 6-10 19 72  
Application for plugging approved 6-11 19 72  
Plugging commenced 8-11 19 72  
Plugging completed 8-28 19 72  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation Depth to top Bottom Total Depth of Well 3398' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,891'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3398' to 3380'. Dumped 5 cu of cement. Mudded hole to 215'. Made 15' of rock bridge. Dumped 3 Yrds. of Ready-Mix Cement, filling to the bottom of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 29 1972

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.  
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb

2809 King St. Hutchinson, Kansas 67501  
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of August, 1972

My commission expires January 5, 1974

Judy Lamb  
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

COPY


15-169-19098-00-00

Company- E. K. CAREY  
Farm- Larson No. 3

SEC. 30 T. 15 R. 3W  
CS<sup>1</sup> SE NW

Total Depth. 3398 K.B.  
Comm. 7-9-51 Comp. 7-24-51  
Shot or Treated.  
Contractor. E.K. Carey  
Issued. 9-15-51

County Saline  
KANSAS



CASING:

8 5/8" 311' com w/250 sx  
5 1/2" 3395' com w/ 75 sx

Elevation. 1288 D.F.

Production. 616 bbls

Figures Indicate Bottom of Formations. K.B.

rotary base & cellar	8
shale	30
sand	40
shale	90
shale, shells	275
lime	530
lime, shale	690
lime	765
salt	768
lime, shale	900
shale, shells	1475
lime, shale	1785
lime	1835
lime, shale	2050
shale, shells	2180
shale, lime	2225
lime	2590
shale, lime	2805
shale, shells	2849
lime	3158
shale	3303
lime	3335
shale	3395
lime	3398

Total Depth

Tops:	
Mississippi lime	2856
Kinderhook shale	3169
Misener sand	3303
Hunton	3305
Maquoketa shale	3335
Maquoketa dolomite	3395

8 5/8" & 5 1/2" head 6.40 below K.B.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 12 1972

CONSERVATION DIVISION  
Wichita, Kansas