


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Saline County, Sec. 30 Twp. 15 Rge. 3 (E) (W)
Location as "NE/CNW&SW" or footage from lines C 111 112
Lease Owner Charles D. Johnson
Lease Name Larson Well No. 1
Office Address McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12-14-62 _____ 19____
Plugging completed 12-17-62 _____ 19____
Reason for abandonment of well or producing formation Deleted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3506 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	310'	None
				5-1/2"	3506'	2738'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded hole to 3360' and dumped 5 sacks of cement @ 3360' with dump bailer. Pulled 5 1/2" casing. Bailed fluid to 300', set 30' rock bridge to 270' and ran 4 yards of ready-mix to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1962

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of December, 1962

Milton J. Volin
Notary Public.

My commission expires May 20, 1964

ROTARY DRILLERS' LOG

Max Gerkin, Operator
18th & 1st Streets
Sioux Falls, South Dakota

Elevation:
Laughlin-Simmons 1880 G.L.
1888 D.F.
1894 K.B.

Larson # 1

"CASING RECORD"

C NW 1/4 NE 1/4 NE 1/4
Sec. 20-158-3W
Saline County, Kansas

8 5/8" - 310', cement 250 sacks.
cement circulated.

Well Commenced: 11-14-50
Well Completed: 11-28-50

5 1/2" - 3506 - 100 1/2

Contractor: E. A. Carey, Contractor (Big #2) Box 620, McPherson, Kansas.
Geologist: Donald Hoy Smith, 5206 East Central, Wichita, Kansas.

Figures Indicate Bottom of Formation K.B.

Rotary Table, Base & Cellar	9	Lime and Shale	2550
Clay	20	Shale	2625
Shale	39	Shale and Lime	2775
Sand	51	Shale	2843
Shale	100	Lime	3160
Shale and Shells	260	Shale	3240
Shells and Lime	310	Red Bed	3260
Lime and Shale	965	Shale	3277
Shale and Shells	1265	Red Rock	3299
Shale and Lime	1530	Shale	3294
Lime and Shale	2091	Lime	3325
Shale and Shells	2220	Shale	3391
Lime	2360	Lime	3500 T.D.

Geologist Top:

Mississippi Lime	2836 (-1552)	Jaquoketa Shale	3224 (-2040)
Kinderhook Shale	3172 (-1888)	" Dolomite	3391 (-2107)
Misener Sand	3295 (-2011)	Viola	3449 (-2165)
Hunton	3298 (-2014)	" Dolomite	3463
		Total Depth	3500 (-2216)

Drill Stem Test:

3391'-95' Open 1 hr. weak blow first 11 minutes. Recovered 30' slightly oil stained mud. 10 min. B.H.P. - 0.

E. A. CAREY, CONTRACTOR

By Herbert Rhoton, Supt.

STATE OF KANSAS)
COUNTY OF MCPHERSON)

On this 29th day of November, 1950, before me, _____
a Notary Public, in and for said County and State, personally appeared
Herbert Rhoton, to me personally known to be the identical person named in
and who executed the foregoing instrument, and acknowledged that he executed
and delivered the same as his free and voluntary act & deed, for the purpose
and consideration therein set forth.

My Commission Expires:

Notary Public