


15-169-00479-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines Saline County, Sec. 30 Twp. 15 Rge. 3 W (E) (W)  
C N/2 T15 SW  
Lease Owner Arvel Smith  
Lease Name Larson Well No. A-2  
Office Address Rt. 1 Towanda, Kansas 67144  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 10-12 19 52  
Application for plugging filed 6-10 19 72  
Application for plugging approved 6-11 19 72  
Plugging commenced 6-28 19 72  
Plugging completed 7-10 19 72  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3409 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2950

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3409' to 3400'. Dumped 5 ex of cement. Mudded hole to 215'. Made 10' of rock bridge. Dumped 3 Yrds. of Ready-Mix cement, filling to the bottom of the collar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 14 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Dasing Pulling Co.  
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.

Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb  
2809 King St. Hutchinson, Kansas 67501  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of July, 19 72

My commission expires January 5, 1974

Judge Lamb  
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-169-00479-00-00

Company- E. K. CAREY  
Farm- Larsen "A"

No. 2


SEC. 30 T. 15 R. 3W  
C N/2 NW SW

Total Depth. 3409  
Comm. 9-30-52

Comp. 10-12-52

County Saline  
KANSAS

Shot or Treated.  
Contractor.  
Issued. 11-28-53



CASING:

8 5/8" 312  
5 1/2" 3401

Elevation 288

Production. 226 BO & 2% wtr

Figures indicate Bottom of Formations.

cellar	2
clay	22
sand	25
shale	34
sand	50
shale & shells	285
lime & shale	835
lime	925
shale & shells	1710
lime & shale	1835
lime	1925
lime & shale	2035
lime	2043
lime & shale	2226
lime	2490
lime & shale	2625
lime & shale	2740
shale & shells	2870
lime Miss.	2900
lime	3180
shale	3200
lime & shale	3403
shale	3409
Total depth	

Tops:	
Mississippi	2878
Kinderhook	3180
Hunton	3210
Maquoketa shale	3330
Maquoketa dolomite	3400

RECEIVED  
STATE CORPORATION COMMISSION

JUN 12 1972

CONSERVATION DIVISION  
Wichita, Kansas