


15-169-00823-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

County. Sec. 30 Twp. 15 Rge. 3 W (E) (W)
Location as "NE/CNWxSWx" or footage from lines C II/2 NE SW
Lease Owner Arval Smith
Lease Name Larson Well No. A-I
Office Address Rt. 1, Towanda, Kansas 67144
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 3-10-1952
Application for plugging filed 6-10-1972
Application for plugging approved 6-11-1972
Plugging commenced 8-14-1972
Plugging completed 8-14-1972
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 10
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Tomax
Producing formation Depth to top Bottom Total Depth of Well 3402' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,852'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3402' to 3380'. Dumped 5 sq of cement. Mudded hole to 215'. Made 10' of rock bridge. Dumped 3 Yrds. Of Ready-Mix Cement, filling to the bottom of the collar.

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of August, 1972
[Signature] Notary Public.
My commission expires January 5, 1974

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COPY

COMPANY E. K. CAREY & JOHNSON BROS.

SEC. 30 T. 15 N. 3W
LOC. CN 1/2 NE SW

FARM LARSON "A"

NO. 1

15-169-00823-0000

TOTAL DEPTH 3402


COUNTY Saline

ODNM. 2-24-51

COMP. 3-10-51

KANSAS

SHOT OR TREATED



CONTRACTOR E. K. Carey

ISSUED 4-14-51

CASING

8 5/8" 318' cem. w/250 ex. oiro.

5 1/2" 3398' cem. w/75 ex.

ELEVATION 1287 D.F.

PRODUCTION Pot 465 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS.

rotary table, base &	
cellar	8
shale	60
sand	65
shale	265
shale & shells	318
lime & shale	860
shale & shells	1515
shale & lime	1740
lime	2063
shale & lime	2085
shale & shells	2185
shale	2218
lime	2555
lime & shale	2705
shale	2850
lime	3172
shale	3305
lime	3329
shale	3398
lime	3402 RTD
Total Depth	

Tops:	
Miss. lime	2850
Kinderhook shale	3158
Misoner sand	3304
Hunton	3307
Maquoketa shale	3335
Maquoketa dolo.	3397
Pay	3397

D.S.T. 3398-3402 Op. 30 min.
Blowing from bottom of 5 ga. bucket
in 3 min. Rec. 310' free oil 15 min.
BHP - 1145#. Initial flowing press. 18#.
Final flowing press. 139#.

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1972
CONSERVATION DIVISION
Wichita, Kansas