


15-169-00821-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 30 Twp. 15 Rge. 3 W (E) (W)
Location as "NE/CNW/SW" or footage from lines C N/2 NW
Lease Owner Arvel Smith
Lease Name Larsen Well No. b-6
Office Address Rt. 1 Towanda, Kansas 67144
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed I-15 1953
Application for plugging filed 6-10 1972
Application for plugging approved 6-11 1972
Plugging commenced 8-15 1972
Plugging completed 8-28 1972
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Tensen
Producing formation Depth to top Bottom Total Depth of Well 3443' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 5 1/2" | | 2,859' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3443' to 3425'. Dumped 5 ex of cement. Mudded hole to 215'. Made 75' of rock bridge. Dumped 3 Yrds. Of Ready-Mix Cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 29 1972

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb

2809 King St Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of August, 1972

Judy Lamb
Notary Public.

My commission expires January 5, 1974

STENCILED

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock,

Wichita, Kansas


15-169-00821-0000
ORIGINAL

DEC 3 1953 Company- REPUBLIC NATURAL GAS COMPANY
Farm- Larson "B" No. 6

SEC. 30 T. 16 R3W
C N $\frac{1}{2}$ NW

Total Depth. 3443
Comm. 12-28-52 Comp. 1-15-53
Shot or Treated.
Contractor. E. K. Carey
Issued. 12-5-53

County Saline
KANSAS



CASING:
8 5/8" 310' cem. w/330 sx
5 1/2" 3443' cem. w/ 50 sx

Elevation. 1287

Production. 100 BO & 19% wtr

Figures indicate Bottom of Formations.

| | |
|--------------------|------|
| cellar | 8 |
| clay & shale | 37 |
| sand | 46 |
| shale & shells | 64 |
| lime & shale | 310 |
| lime | 700 |
| shale & lime | 1700 |
| lime | 2038 |
| sandy lime | 2104 |
| shale & lime | 2155 |
| shale | 2220 |
| lime | 2260 |
| lime sandy | 2270 |
| lime | 2575 |
| lime & shale | 2675 |
| lime | 2710 |
| lime & shale | 2845 |
| lime | 3167 |
| shale & lime | 3170 |
| shale | 3298 |
| lime | 3330 |
| shale maquoketa | 3393 |
| dolomite maquoketa | 3443 |
| Total Depth | |

SCOUT TOPS:

| | |
|--------------------|------|
| Hunton | 3301 |
| Maquoketa Dolomite | 3392 |

Core #1 3393-3421' full rec.
Core #2 3421-3443' 17' rec.

RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1972

CONSERVATION DIVISION
Wichita, Kansas