


15-169-00824-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW4" or footage from lines Saline County. Sec. 30 Twp. 15 Rge. 3 W (E) (W)
Location as "NE/CNW/SW4" or footage from lines SW SW NE
Lease Owner Ray Perera
Lease Name Larsen Well No. 2
Office Address 100 Laurel Ct. McPherson, Kansas 67460
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed II-5 1951
Application for plugging filed 7-21 1972
Application for plugging approved 7-22 1972
Plugging commenced 8-7 1972
Plugging completed 8-14 1972
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3405' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2858'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3405 to 3390'. Made 15' of rock bridge. Dumped 3 1/2 Yrds. of Ready-Mix Cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of August, 1972
Judy Lamb Notary Public.
My commission expires January 5, 1974

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-169-00824-00-00
COPY

Company- GEORGE E. SEREL
Farm- Larson No. 2

SEC. 30 T. 15 R. 3W
SW SW NE

Total Depth. 3407'
Comm. 10-21-51 Comp. 11-5-51
Shot or Treated.
Contractor. E. K. Carey
Issued. 8-15-59

County Saline
KANSAS



Elevation. 1287' DF

Production. 77 BOPD & 25% Wtr.

CASING:

3 5/8" 305' cem w/250 sx.
5 1/2" 3404' cem w/75 sx.

Figures Indicate Bottom of Formations.

base & cellar	0
clay & shale	20
shale	40
sand	55
shale	250
sand	252
lime & shale	315
lime	480
lime & shale	530
lime	680
lime & shale	1025
lime	1040
shale & lime	1660
lime & shale	1895
lime & shale strks	1955
lime & shale	2275
lime	2730
lime & shale	2755
lime, shale	2850
shale	2858
lime	3170
lime, shale	3230
shale	3305
lime	3338
shale & lime	3400
shale	3404
lime	3405 1/2 RTD
lime	3407
Total Depth	

TOPS:

Mississippi	2862
Kinderhook	3176
Misener	3307
Hunton	3310
Sylvian Shale	3334
Maquoketa Dolomite	3376
Maquoketa Shale	3395
Viola	3404

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1972
CONSERVATION DIVISION
Wichita, Kansas