


15-169-00825-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines Salina County, Sec. 30 Twp. 15 Rge. 3 W (E) (W)

Lease Owner Ray Parera

Lease Name ##### Larsen Well No. 3

Office Address 100 Laurel Ct. Mc Pherson, Kansas 76460

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 5-2 1952

Application for plugging filed 7-21 1972

Application for plugging approved 7-22 1972

Plugging commenced 8-9 1972

Plugging completed 8-14 1972

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Tomer

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3400' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 5 1/2" | | 2876' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3400' to 3330'. Dumped 5 sx of cement. Made 15' of rack bridge. Dumped 3 1/2 Yrds. of Ready-Mix Cement, filling to the bottom of the collar.

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.

Address 2809 King St. Hutchinson, Kansas 67460

STATE OF Kansas, COUNTY OF Rawl, ss. Art Lamb (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb

2809 King St. Hutchinson, Kansas 67460
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of August, 1972

My commission expires January 5, 1974

Judy Lamb
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-169-00825-00-00

Company- GEORGE E. SEREL
Farm- Larson No. 3

SEC. 30 T. 15 R. 3W
C W/2 W/2 NE

Total Depth. 3400'
Comm. 4-16-52 Comp. 5-2-52
Shot or Treated.
Contractor. E. K. Carey
Issued. 8-15-59

County Saline
KANSAS



CASING:

8 5/8" 345' cem w/250 sx.
5 1/2" 3395' cem w/75 sx.

Elevation. 1286' DF

Production. 86 BOPD & Tr. Wtr.

Figures indicate Bottom of Formations.

| | |
|----------------|----------|
| cellar | 7 |
| clay | 33 |
| sand | 48 |
| shale | 60 |
| shale & shells | 260 |
| lime & shale | 345 |
| lime | 350 |
| lime & shale | 905 |
| shale & lime | 1085 |
| shale & shells | 1485 |
| shale & lime | 1720 |
| lime | 1775 |
| lime & shale | 2125 |
| shale & lime | 2248 |
| lime | 2540 |
| lime & shale | 2670 |
| shale & lime | 2710 |
| shale & shells | 2835 |
| shale & lime | 2842 |
| lime | 3176 |
| shale | 3308 |
| lime (H) | 3340 |
| shale | 3352 |
| shale & lime | 3395 |
| lime | 3400 RTD |
| Total Depth | |

TOPS:

| | |
|---------------------|------|
| Kansas City (scout) | 2248 |
| Mississippi | 2842 |
| Kinderhook | 3174 |
| Hunton | 3302 |
| Maquoketa Shale | 3314 |
| Maquoketa Dolomite | 3395 |

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1972
CONSERVATION DIVISION
Wichita, Kansas