

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-169-00818 00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

County. Sec. Twp. Rge. (E) (W)

Location as "NE/CNW&SW&" or footage from lines

Lease Owner

Lease Name SWENSON Well No. 2

Office Address

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced NOV 24 1958

Plugging completed DEC 1 1958

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well GILBERT TOMAN

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

MUDDING BACK TO 3395 FT. DUMPED 5 SACKS OF  
CEMENT. SHOT PIPE OFF AT 2817 FT. PULLED  
PIPE AND MUDDING HOLE TO 300 FT. SET ROCK  
BRIDGE AND DUMPED 20 SACKS OF CEMENT. FINISHED  
MUDDING HOLE AND DUMPED 10 SACKS OF CEMENT AT  
TOP.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 13 1959

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF KANS. COUNTY OF RENO ss.

EMPLOYEE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Best Self  
HUTCHINSON KANS. R. (Address) 0. 4

SUBSCRIBED AND SWORN TO before me this 3RD DAY of DECEMBER, 1958

My commission expires AUGUST 12-61

Worthy Self Notary Public.

PLUGGING  
FILE NO. 30 T 15 R 3 W  
BOOK PAGE 4 LINE 16

15-169-00818-00-00

# STERLING DRILLING CO.

STERLING, KANSAS

WELL LOG ----- SWENSON #2

Location - NW/4 NW/4 SE/4 of Section 30-15S-3W, Smolan Pool,  
Saline County, Kansas

Owner - R. O. Keys, Operator  
Rotary Drilling Contractor - Sterling Drilling Company  
Cable Tools Contractor -

Commenced - 12-22-51  
Completed - 1-7-52 (w/r)  
                  - (w/c.t.)

Total Depth - 3402 (w/r)  
                  - (w/c.t.)

### LOG

0- 275	Sand and Shale
275- 326	Shale and Shells
326- 333	Anhydrite
333- 825	Lime
825-1550	Shale and Lime
1550-1880	Lime
1880-2295	Lime and Shale
2295-2670	Lime
2670-2865	Lime and Shale
2865-2965	Lime
2965-2995	Lime and Shale
2995-3170	Lime
3170-3402	Shale
3402-Total	Depth

### CASING RECORD

339' of 8-5/8" Surface Pipe  
Cemented with 250 sacks cement  
  
3419' of 5" O. D. Casing  
Cemented with 75 sacks cement  
(Set 1' off bottom)

### PRODUCTION:



RECEIVED  
STATE CORPORATION COMMISSION  
FEB 13 1959  
CONSERVATION DIVISION

**PLUGGING**  
FILE SEC. 30 T. 15 R. 3W  
BOOK PAGE 4 LINE 16