


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Saline County, Sec. 24 Twp. 15 Rge. 3 W (E) (W)  
Location as "NE/CNWxSWx" or footage from lines C NE NW

Lease Owner Cal Jones  
Lease Name Carlin Well No. 3  
Office Address P.O. Box 5 Canton, Kansas 67428

Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed II-22 19 62  
Application for plugging filed 5-3 19 69  
Application for plugging approved 5-6 19 69  
Plugging commenced 6-6 19 69  
Plugging completed 6-9 19 69  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Tom  
Producing formation Depth to top Bottom Total Depth of Well 3296' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,751'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3296' to 3280'. Dumped 5 ax of cement. Mudded hole to 280'. Made 10' of rock bridge. Dumped 25 ax of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 ax of cement, filling to the bottom of the collar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 13 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.  
Art Lamb (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Art Lamb*  
2809 King St Hutchinson, Kansas 67501  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of June, 19 69

*Judge Lamb*  
Notary Public.

My commission expires January 5, 1970

KANSAS GEOLOGICAL SOCIETY 15-169-00474-00-00  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

COPY


COMPANY CAL JONES

SEC. 24 T. 15 R. 3W  
 LOC. C NE NW

FARM Carlin NO. 3

TOTAL DEPTH 3296'  
 COMM. 10-16-62 COMP. 11-22-62  
 BSHOT OR TREATED  
 CONTRACTOR Melland Drig.  
 ISSUED 10-15-66

COUNTY Saline



CASING  
 20 10  
 15 8 " 265' cem w/ 133 sx  
 12 6  
 13 5 " 3296' cem w/ 50' sx

ELEVATION 1268' RB

PRODUCTION 25 BOPD  
 (Maq. DoI 3250-56)

FIGURES INDICATE BOTTOM OF FORMATIONS

COMPLETE DRILLERS LOG NOT AVAILABLE

TOPS: SMP  
 Hunton 3150  
 Maquokta shale 3179  
 Maquoketa Dolomite 3249  
 Viola 3291  
 Total Depth 3296 RTD

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 5 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas