

15-169-19105-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Saline County, Sec. 23 Twp. 15 Rge. 3W (E) (W)

Location as "NE/CNWSW" or footage from lines C SE NE

Lease Owner Arvel Smith

Lease Name Carlin Well No. "A"

Office Address 534 North Tallyrand Wichita, Kansas 67206

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 5-23 19 61

Application for plugging filed 6-3 19 69

Application for plugging approved 6-5 19 69


Plugging commenced 6-12 19 69

Plugging completed 6-13 19 69

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3300' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,718'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3300' to 2770'. Dumped 5 sx of cement. Mudded hole to 275'. Made 10' of rock bridge. Dumped 25 sx of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the celler.

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.

Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of June 19 69

My commission expires January 5, 1970
Notary Public.

15-169-19105-00-00

Casing Record

Location: C SE NE
Section: 23-15-3W
Saline County, Kansas
Farm: Carlin Estate "A"
Well Owner: Earl Wakefield
Contractor: White & Ellis Drig., Inc.
Started: 5/23/61
Completed:

8 5/8	277' Cemented w/175 sacks
5 1/2	3299' Cemented w/75 sacks
T.D.	3300'
Kelly Bushing Measurement	5' above ground level.
FORMATION	DEPTH
Soil	0-40
Sdy. Clay	75
Shale & Lime stks.	180
Lime	290
Anthhydrite	355
Red rock	380
Lime & Shale stks.	1650
Lime	1900
Shale & Lime	2090
Lime	2295
Lime & Shale stks.	2515
Shale	2738
Lime	2956
Shale	3035
Shale & Lime	3220
Shale	3237
Dolomite	3276
Lime	3300

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1969
CONSERVATION DIVISION
Wichita, Kansas

TOPS

Kansas City	2090
Mississippi	2738
Maquoketa	3237
Viola	3276