

15-169-00214-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Saline County, Sec. 23 Twp. 15 Rge. 3W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE SE

Lease Owner Cal Jones

Lease Name Miller Well No. I

Office Address P.O. Box 5 Canotn, Kansas 67428

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 5-I 1961

Application for plugging filed 5-3 1969

Application for plugging approved 5-5 1969

Plugging commenced 6-10 1969

Plugging completed 6-II 1969

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Gilbert Toman

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3284' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,723'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with rock. Rock from 3284' to 3260'. Dumped 5 sx of cement. Mudded hole to 275'. Made 10' of rock bridge. Dumped 25 sx of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.

Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.

Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb

2809 King St. Hutchinson, Kansas 67501

(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of June, 1969

My commission expires January 5, 1970

Judy Lamb
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-169-00214-00-00
COPY

Company- CAL JONES
Farm- Miller No. 1

SEC. 23 T. 15 R. 3W
C NE SE

Total Depth. 3323'
Comm. 4-24-61 Comp. 5-1-61
Shot or Treated.
Contractor. Melland Drilling Co.
Issued. 10-7-61

County Saline
KANSAS



Elevation. 1277' RB

Production. 30 BOPD

CASING:
8 5/8" 278' cem w/200 sx.
5 1/2" 3284' cem w/75 sx.

Figures indicate Bottom of Formations.

surface soil, shale & clay	110
shale & shells	211
Anhydrite	278
lime & shale	1010
shale & shells	1675
lime & shale	1915
shale	2095
lime & shale	2500
shale	2761
Mississippi Lime	2945
lime	3005
lime & shale	3065
shale & lime	3215
lime & shale	3280
lime	3284 RTD
lime	3323
Total Depth	

TOPS: SCOUT	
Lansing	2094
Mississippi	2747
Kinderhook	2995
Hunton	3156
Maquoketa Shale	3166
Dolomite	3241
Viola	3282

RECEIVED
STATE CORPORATION COMMISSION
MAY 5 1969
CONSERVATION DIVISION
Wichita, Kansas

no plus
record