


15-169-30036-00-00  
Form CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Location as "NE/CNWxSWx" or footage from lines Saline County, Sec. 21 Twp. 15 Rge. 3 (E) (W) X  
SE NW  
Lease Owner Walter J. Nelson  
Lease Name Ericson Well No. 1  
Office Address Salina, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) RECEIVED  
Date well completed \_\_\_\_\_ STATE CORPORATION COMMISSION 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved JAN 26 1970 19\_\_\_\_  
Plugging commenced 1-3-70 CONSERVATION DIVISION 19\_\_\_\_  
Plugging completed 1-12-70 Wichita, Kansas 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3374 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	285	None
				5 1/2	None	2520', 67


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved in and rigged up unit. Cleaning out cellar.  
Sanded to 3285' and dumped 5 sacks of cement. Working pipe, lost shot in hole and fished out same.  
Working pipe, shot pipe at 2800' and 2700'. Lost shooting line in hole, fishing for same.  
Fished out line. Put on new line and shot pipe at 2630'. Lost more line, pipe not loose. Working pipe, mud came in at 1495'. Had 31" tension at 3000 psi.  
Allied Cementing pumped a plug to a hole in the casing at 1610'. Fished the plug and wire line to clear hole. Build shot and shot off at 2504', pipe loose. Build slide and rack and worked on the friction clutch.  
Laid down 46 joints of 5 1/2" casing. Laid down rest of casing - 32 joints. Cleared hole for plugging. Set rockbridge from 280' to 265', couldn't get hold of pluggers. Plugged well with 4 yards of ready mix concrete.

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
P. O. Box 221 Great Bend, Kansas  
(Address)



Subscribed and sworn to before me this 23 day of January, 19 70  
Gilbert Toman  
Notary Public.