

15-169-30035-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plot

Saline County, Sec. 21 Twp. 15 Rge. 3 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines CS/2 SW NE  
Lease Owner Tom C. Brown  
Lease Name Miller Well No. 1  
Office Address Lindsborg, Kans.  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed July 28 19 66  
Application for plugging filed WELL PLUGGING BLIND 19 71  
Application for plugging approved June 3 19 71  
Plugging commenced June 19 71  
Plugging completed June 21 19 71  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production May 1970 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott  
Producing formation Maquoketa Dol Depth to top 3265 Bottom 3271 Total Depth of Well 3457 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Maquoketa Dol	Oil	3265	3271	5 1/2	3457	1199.35

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded back in the hole to 3200'. Dumped 5 sacks of cement from 3200 to 3150'. Shot pipe off at 1199.35'. Pulled pipe and mudded hole to 345'. Set rock bridge from 345' to 335'. Cemented from 335' to top of surface.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 29 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self  
Address Hutchinson, Kans.

STATE OF Kans., COUNTY OF Reno, ss.  
Employee (employee of owner) or (owner or operator) of the above-described well. I, Bert Self, sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self  
R. R. #4, Hutchinson, Kans. 67501  
(Address)

Subscribed and sworn to before me this 22nd day of June, 1971



My commission expires October 18, 1973

Notary Public.

15-169-30035-00-00

STENCILED

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

ORIGINAL  
6P


JAN 6 1968  
COMPANY WEEKS & SHAW

SEC. 21 T. 15 R. 3W  
LOC. CS/2 SW NE

FARM Miller NO. 1

TOTAL DEPTH 3462'  
COMM. 6-15-66 COMP. 7-28-66  
SHOT OR TREATED  
CONTRACTOR Blackstone Drlg.  
ISSUED 1-6-68

COUNTY Saline



CASING  
20 10  
15 8 5/8 325' w/100 sx cem.  
12 6  
13 5 1/2 3457' w/100 sx cem.

ELEVATION 1272' KB

PRODUCTION Pmp 25 BO &  
75 BWPD (VIO 3340-50)

FIGURES INDICATE BOTTOM OF FORMATIONS

COMPLETE DRILLERS LOG NOT AVAILABLE.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 3 1971  
CONSERVATION DIVISION  
Wichita, Kansas

TOPS: SCOUT SAMPLE  
Mississippi 2741  
Kinderhook 3020  
Hunton 3170  
Maquoketa 3265  
Viola 3320  
Simpson shale 3438  
Simpson sand 3457