

15-169-20009-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Saline County, Sec. 21 Twp. 15 Rge. 3 (E) V (W)
Location as "NE/CNW/SE/SW" or footage from lines SE SE NE
Lease Owner Tom C. Brown
Lease Name Miller Well No. 2
Office Address Lindsborg, Kans.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Aug. 27 1971
Application for plugging filed June 3 1971
Application for plugging approved June 3 1971
Plugging commenced June 21 1971
Plugging completed June 21 1971
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production Mar 1971
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Maquoketa Depth to top 3270 Bottom 3282 Total Depth of Well 3282 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Maquoketa	Oil	3270	3279	4 1/2	3278	2786.5

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back in the hole to 3200' and dumped 5 sacks of cement from 3200' to 3150'. Shot pipe off at 2786.50'. Pulled pipe and mudded hole to 330'. Set rock bridge from 330' to 320'. Finished filling hole from 320' to top with cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1971
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Bert Self
Address Hutchinson, Kans

STATE OF _____ Kans _____, COUNTY OF _____ Reno _____, ss.

_____, Employee _____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Bert Self
R. R. #4, Hutchinson, Kans. 67501

(Address)

Subscribed and Sworn to before me this 22nd day of June, 1971

My commission expires October 18, 1973

Notary Public.

BUREAU
15-169-20009-00-00

MAY 11 1958

COMPANY WEEKS & SHAW

DEC. 21 Y. 15 M. 3W

FARM Miller

NO. . . 2

LOC. SE .SE NE

LOC. SE .SE NE

TOTAL DEPTH 3282'

COMM. 8-20-67

COMP. 8-27-67

SHOT OR TREATED

CONTRACTOR Blackstone Drilling

ISSUED 5-11-68

COUNTY Saline

KANBAM

CASINO

20

10

15

B

12

6

13

5

4½" 3278'

ELEVATION 1270' KRB

PRODUCTION P 130 BOPD ~~NW~~

Viola 3278-82

FIGURES INDICATE BOTTOM OF FORMATIONS

0	to	35	Shale
35	to	60	Sand
60	to	290	Shale & Shells
290	to	310	Lime
310	to	450	Shale & Lime
450	to	685	Lime
685	to	750	Lime & Shale
750	to	1145	Shale & Shells
1145	to	1645	Shale & Lime
1645	to	1875	Lime
1875	to	2180	Shale & Lime
2180	to	2465	Lime
2465	to	2600	Lime & Shale
2600	to	2749	Shale & Lime
2749	to	3025	Mississippi
3025	to	3178	Kinderhook
3178	to	3210	Hunton
3210	to	3270	Maquoketa Shale
3270	to	3279 1/2	Maquoketa Dolemite
		3279 1/2	T.D.
		3282	DDTD

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1971
CONSERVATION DIVISION
Wichita, Kansas

Cut 12 1/4 in. hole to 310 ft. and run 312 ft. of 8 5/8 in. surface pipe and set on bottom at 310 ft. Cemented with 225 sx. cement. Plug down at 7:45 P.M., August 20, 1967. Cut 7 7/8 in. hole to 3279 1/2 ft. and run 3284 ft. of 4 1/2 in. casing, and cemented with 50 sacks cement 2 foot off bottom at 3278 ft. Plug down at 3:30 A.M., August 27, 1967.

TOPS: Mississippi - 2749' Kinderhook - 3025' Hunton - 3178'
Maquoketa Shale - 3210' Maquoketa Dolemite - 3270'

Measurements taken from K.B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Miller #2, located on the SE/4 SE/4 NE/4 of Sec. 21-15S-3W, Saline County, Kansas as reflected by the files of BLACKSTONE DRILLING, INC.

H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas
this 29th day of May, 1967.

Ruth McVay - Notary Public

Expires: December 18, 1969.

