


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Saline County. Sec. 21 Twp. 15 Rge. 3 (E) (W)
C SW SW
Location as "NE/CNW*SW*" or footage from lines _____
Lease Owner Walter J. Nelson
Lease Name Stanley #1 Well No. _____
Office Address Salina, Kansas 67401
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 11/3/71 _____ 19____
Plugging completed 11/8/71 _____ 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3390 Feet
Show formation and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	346	none
				5 1/2"	3390	2639'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, ran sand to 3350' and dumped 5 sacks of cement.
Shot pipe at 2682', pulled 83 joints. Bailed hole to 315', set
rock bridge to 300'. Fluid came up hole, bailed hole down, dumped
25 sacks of cement. Mudded to 40', 10' rock bridge and dumped 10
sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JAN 14 1972
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

Subscribed and sworn to before me this 9th day of November, 19 71
Margaret Melcher
NOTARY PUBLIC
Rice County, Kansas
My commission expires Feb. 15, 1975



Margaret Melcher
Notary Public.

STENCILED

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

15-169-00469-00-00
ORIGINAL

OCT 15 1966


COMPANY WALTER J. NELSON

SEC. 21 15 R. 3W
LOC. C SW SW

FARM Stanley NO. 1

COUNTY Saline
KANSAS

TOTAL DEPTH 3390'
COMM. 4-2-64 COMP. 6-11-64
SHOT OR TREATED
CONTRACTOR Clark Knight
ISSUED 10-15-66



CASING

20 10
15 8" 346' cem w/ 75 sx
12 6
13 5" 3390'

ELEVATION 1273' DF

PRODUCTION 25 BOPD PLUS WTR
(Maq Dolo 3305-10)

FIGURES INDICATE BOTTOM OF FORMATIONS

COMPLETE DRILLERS LOG NOT AVAILABLE

TOPS: SMP
Hunton 3283
Maquoketa shale 3294
Maquoketa Dolomite 3303
Viola 3371
Total Depth 3390

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1971
CONSERVATION DIVISION
Wichita, Kansas