



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

November 22, 1969

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 26 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bert Self of Self Casing Pulling Co. has this
date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Tom C. Brown

Complete Address: Box 387, Lindsborg, Kansas 67456

Lease Name: Andrew Nelson Well No. 1

Location: SW NW NE Sec. 24 Twp. 15 Rge. 3 (E)(W) X

County: Saline Total Depth 3341' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3325' and cement with 3 sacks cement.

Fill hole with mud to 240'. Set rock bridge from 240' to 230' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set

rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent