



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

May 20, 1969

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 2 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Art Lamb of Lamb Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Cal Jones

Complete Address: Box 5, Canton, Kansas 67428

Lease Name: Miller Well No. 2

Location: C SE SE Sec. 23 Twp. 15 Rge. 3 (E)(W) X

County: Saline Total Depth 3296' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 3280' and cement with 5 sacks cement.

Fill hole with mud to 260'. Set rock bridge from 260' to 250' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set

rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


 Conservation Division Agent