



15-169-19110-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 2 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bert Self of Self Casing Pulling Co. has this  
date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Tom C. Brown

Complete Address: Box 387, Lindsborg, Kansas 67456

Lease Name: Richter Well No. 2

Location: SW SW SW Sec. 19 Twp. 15 Rge. 3  (W)  X

County: Saline Total Depth 3409' Oil Well  X

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3390' and cement with 5 sacks cement.

Fill hole with mud to 310'. Set rock bridge from 310' to 300' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

  
Conservation Division Agent