



15-169-19113-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

April 20

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Tom C. Brown

Complete Address: Box 387, Lindsborg, Kansas

Lease Name: Muir Well No. 2

Location: C 1/4 NE Sec. 13 Twp. 15 Rge. 3 (E) (W) X

County Saline Total Depth 3256' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3240' and cement with 3 sacks.

Fill hole with mud to 210'. Set rock bridge from 210'

to 200' and cement with 20 sacks. Fill hole with mud to

40'. Set rock bridge from 40' to 30' and cap hole with

10 sacks cement.

Very truly yours,

Conservation Division Agent