



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

March 9, 1963

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Art Lamb of Lamb Casing Pulling Co. has this
 date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Don McKellar Oil Operations

Complete Address: P.O. Box 173, Salina, Kansas

Lease Name: Gunnerson Well No. 1

Location: NW NW SE Sec. 35 Twp. 15 Rge. 3 (S) (W) X

County Saline Total Depth 3363' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lamb was instructed to plug the well as follows:

Push 4 1/2" plug to 3290'. Fill hole with sand to 3280' and
cement with 5 sacks. Fill hole with mud to 260'. Set rock
bridge from 260' to 250' and cement with 20 sacks.
Fill hole with mud to 40'. Set rock bridge from 40' to
30' and cap hole with 10 sacks cement.

Very truly yours,

[Signature]
 Conservation Division Agent