

15-169-00835-00-00

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

February 24, 1966

STATE CORPORATION COMMISSION  
WICHITA, KANSAS

MAR 4 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bert Self of Self Casing Pulling Co. has this  
date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Inc.

Complete Address: 410 Fourth Nat'l Bank Bldg., Wichita, Kansas

Lease Name: Ahlstedt Well No. 2

Location: SW SW NE Sec. 32 Twp. 15 Rge. 3 (W) X

County Saline Total Depth 3378' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3360' and cement with 5 sacks.

Fill hole with mud to 215'. Set rock bridge from 215' to 200' and

cement hole to base of cellar with 2 1/2 yards ready mix cement.

Very truly yours,

Conservation Division Agent