

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20310-00-01
Spot: NESENENE Sec/Twnshp/Rge: 34-21S-19E
4570 feet from S Section Line, 75 feet from E Section Line
Lease Name: KELLSTADT Well #: C 37
County: ANDERSON Total Vertical Depth: 855 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	20		
PROD	2.5	848		

Well Type: EOR UIC Docket No: E11406.24 Date/Time to Plug: 01/10/2012 12:00 PM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string out, tie onto well, and squeeze cement into formation until desired pressure is achieved.
Cut pipe off 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 01/10/2012 12:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1" pipe to TD, circulated portland cement to surface, pulled 1" pipe out, hooked on to 2-7/8" casing and squeezed cement into well, shut in at 750 psi. Contractor indicated that they used 45 sacks cement to plug well.

Perfs:

Top	Bot	Thru	Comments
823	837		SQUIRREL

RECEIVED

FEB 13 2012 JA

KCC Chanute Dist #3

Remarks:

Plugged through: TBG

District: 03

Signed

(TECHNICIAN)

RECEIVED

FEB 16 2012

KCC WICHITA

Form CP-2/3