

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20956-00-00
Spot: SESESWNW Sec/Twnshp/Rge: 35-21S-19E
2717 feet from S Section Line, 4007 feet from E Section Line
Lease Name: SUMMERS Well #: 179
County: ANDERSON Total Vertical Depth: 851 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	25		3 SX
PROD	2.5	850		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/16/2012 12:00 PM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string, tie onto well and squeeze cement until desired pressure is achieved. Cut pipe off 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE
Date/Time Plugging Completed: 01/16/2012 11:00 AM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1" to TD, circulated portland cement to surface, pulled 1" out, topped off well, hooked on to 2-1/2" and squeezed cement into casing, shut in at 750 psi. Contractor indicated that they used 45 sacks cement to plug well.

Perfs:

Top	Bot	Thru	Comments
817	851		SQUIRREL

RECEIVED
FEB 13 2012 JA
KCC Chanute Dist #3

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)

RECEIVED Form CP-2/3
FEB 16 2012 2/20/12
KCC WICHITA