

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20140-00-00
Spot: NENWSENW Sec/Twnshp/Rge: 35-21S-19E
3844 feet from S Section Line, 3509 feet from E Section Line
Lease Name: SUMMERS Well #: 17-P
County: ANDERSON Total Vertical Depth: 839 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	22		
PROD	2	835		25 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/16/2012 12:00 PM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Revd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string, tie onto well and squeeze cement until desired pressure is achieved. Cut pipe off 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 01/17/2012 2:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1" and packer down 2" to 750', squeezed cement into well and shut in at 750 psi. Left well shut in until next day, pulled 1" and packer out, ran 1" to TD, circulated portland cement to surface, pulled 1' out, washed 1' down backside of 2" to 375', circulated cement to surface, pulled 1" out, topped off well. Contractro indicated that they used 114 sacks cement to plug well.

Perfs:

Top	Bot	Thru	Comments
800	825		SQUIRREL

RECEIVED

FEB 13 2012

JA

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)

RECEIVED

Form CP-2/3

FEB 16 2012

KCC WICHITA

2/21/12