

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-01975-00-00  
Spot: SESEWNWE Sec/Twnshp/Rge: 34-21S-19E  
4107 feet from S Section Line, 1562 feet from E Section Line  
Lease Name: KELLSTADT Well #: 16  
County: ANDERSON Total Vertical Depth: 866 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10	16		
PROD	6.25	813		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/09/2012 12:00 PM  
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.  
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Wash work string to bottom, cement to surface. Pull work string out, tie on to well, and squeeze cement into formation until desired pressure is achieved. Cut well off 3' below ground level, cap, and backfill

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE  
Date/Time Plugging Completed: 01/09/2012 11:00 AM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1" pipe to TD, circulated portland cement to surface, washed 1" pipe down outside of 6-1/4" to 550', circulated portland cement to surface, pulled both 1" strings out, topped off well. Contractor indicated that they used 266 sacks cement to plug well.

Perfs:

Top	Bot	Thru	Comments
834	860		

RECEIVED

FEB 13 2012 JA

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

  
(TECHNICIAN)

RECEIVED Form CP-2/3

FEB 16 2012

KCC WICHITA

2/21/12