

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20044-00-00
Spot: NESEWNNE Sec/Twnshp/Rge: 34-21S-19E
4399 feet from S Section Line, 1454 feet from E Section Line
Lease Name: KELLSTADT Well #: 29
County: ANDERSON Total Vertical Depth: 870 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	21		0
PROD	4	870		25 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/10/2012 12:00 PM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Wash work string to bottom, cement to surface. Pull work string out, tie on to well, and squeeze cement into formation until desired pressure is achieved. Cut well off 3' below ground level, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 01/10/2012 11:00 AM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1' to TD, circulated portland cement to surface, pulled 1" out, topped of well, hooked on to 4" and squeezed cement into well, circulated cement to surface on backside. Contractor indicated that they used 120 sacks cement to plug well.

Perfs:

Top	Bot	Thru	Comments
840	860		SQUIRREL

RECEIVED

FEB 13 2012

KCC Chanute Dist #3

JA

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)

RECEIVED

FEB 16 2012

KCC WICHITA

Form CP-2/3

2/21/12