

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-20523-00-00  
Spot: NWNENWNE Sec/Twnshp/Rge: 34-21S-19E  
5030 feet from S Section Line, 1750 feet from E Section Line  
Lease Name: KELLSTADT Well #: 5176  
County: ANDERSON Total Vertical Depth: 862 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 6.625 | 25         |             |          |
| PROD 2 |       | 838        |             |          |

Well Type: EOR UIC Docket No: E11406.20 Date/Time to Plug: 01/05/2012 12:00 PM  
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.  
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string out, tie onto well, and squeeze cement until desired pressure is achieved. Cut pipe off 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE  
Date/Time Plugging Completed: 01/05/2012 3:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1" pipe to TD, circulated portland cement to surface, pulled 1" out, topped off well, hooked on to 2" and squeezed cement into well, shut in at 750 psi. Contractor indicated that they used 30 sacks cement to plug well.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 838 | 862 |      | SQUIRREL |

RECEIVED

FEB 13 2012 JA

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

  
(TECHNICIAN)

RECEIVED

Form CP-2/3

FEB 16 2012

KCC WICHITA

cc to WIC 2/17/12

2/21/12