

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-21735-00-00  
Spot: NWNWNWNE Sec/Twnshp/Rge: 34-21S-19E  
4980 feet from S Section Line, 2475 feet from E Section Line  
Lease Name: KELLSTADT Well #: 1-I-81  
County: ANDERSON Total Vertical Depth: 848 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	50		
PROD	2	833		

Well Type: EOR UIC Docket No: E11406.6 Date/Time to Plug: 01/06/2012 12:00 PM  
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.  
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface, and squeeze cement until desired pressure is achieved. Cut off pipe 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE  
Date/Time Plugging Completed: 01/06/2012 2:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1" pipe to TD, circulated portland cement to surface, pulled 1" out, topped off well, hooked on to 2" and squeezed cement into well, shut in at 500 psi. Contractor indicated that they used 30 sacks cement to plug well.

Perfs:

Top	Bot	Thru	Comments
834	848		SQUIRREL

RECEIVED JA

FEB 13 2012

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

  
(TECHNICIAN)

RECEIVED

Form CP-2/3

FEB 16 2012

KCC WICHITA

cc to UIC 2/17/12

2/21/12