

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-21737-00-00
Spot: NWSWNWNE Sec/Twnshp/Rge: 34-21S-19E
4360 feet from S Section Line, 2475 feet from E Section Line
Lease Name: KELLSTADT Well #: 3181
County: ANDERSON Total Vertical Depth: 849 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	22		3 SX
PROD	2.875	820		126 SX

Well Type: EOR UIC Docket No: E11406.15 Date/Time to Plug: 01/06/2012 12:00 PM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Wash work string to bottom, cement to surface. Pull work string out, tie on to well, and squeeze cement into formation until desired pressure is achieved. Cut well off 3' below ground level, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE
Date/Time Plugging Completed: 01/06/2012 11:00 AM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1" pipe to TD, circulated portland cement to surface, pulled 1" pipe and topped off well, hooked to 2-7/8" and squeezed cement into well, shut in at 700 psi. Contractor indicated that they used 30 sacks cement to plug well.

Perfs:

Top	Bot	Thru	Comments
820	849		

RECEIVED

FEB 13 2012

KCC Chanute Dist. #3

JA

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

rec to UIC 2/17/12

RECEIVED Form CP-2/3

FEB 16 2012 2/20/12

KCC WICHITA