

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-20350-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 35-21S-19E  
3630 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: SUMMERS Well #: 1175  
County: ANDERSON Total Vertical Depth: 856 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.625	20		
PROD	3	824		

Well Type: EOR UIC Docket No: E06421.4 Date/Time to Plug: 01/05/2012 12:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string, tie onto well and squeeze cement until desired pressure is achieved. Cut pipe off 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE  
Date/Time Plugging Completed: 01/05/2012 11:00 AM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1' to TD, circulated portland cement to surface, pulled 1" out, topped off well, hooked on to casing and squeezed cement into well, shut in at 600 psi. Contractor indicated that they used 55 sacks cement to plug well.

Perfs:

Top	Bot	Thru	Comments
795	823		SQUIRREL

RECEIVED

FEB 13 2012 JA

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

  
(TECHNICIAN)

✓ cctb UMC 2/17/12

RECEIVED Form CP-2/3  
FEB 16 2012 2/26/12  
KCC WICHITA