

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20365-00-00
Spot: NWSENW Sec/Twnshp/Rge: 35-21S-19E
3570 feet from S Section Line, 3560 feet from E Section Line
Lease Name: SUMMERS Well #: 2-1-75
County: ANDERSON Total Vertical Depth: 835 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	20		
PROD	3	811		

Well Type: EOR UIC Docket No: E06421.9 Date/Time to Plug: 01/06/2012 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Revd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string, tie onto well and squeeze cement until desired pressure is achieved. Cut off pipe 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 01/06/2012 2:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor hooked on to 3" casing and squeezed portland cement into well, shut in at 800 psi.
Contractor indicated that they used 66 sacks cement to plug well.

Perfs:

Top	Bot	Thru	Comments
811	835		SQUIRREL

RECEIVED

FEB 13 2012 JA

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

cc to UIC 2/17/12

RECEIVED
Form CP-2/3
FEB 16 2012
KCC WICHITA