

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-22698-00-01  
Spot: SWSWNW Sec/Twnshp/Rge: 35-21S-19E  
3300 feet from S Section Line, 4775 feet from E Section Line  
Lease Name: SUMMERS Well #: 1185  
County: ANDERSON Total Vertical Depth: 843 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	21		5 SX
PROD	2.875	823		125 SX

Well Type: EOR UIC Docket No: E06421.6 Date/Time to Plug: 01/05/2012 12:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Revd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Wash work string to bottom, cement to surface. Pull work string out, tie on to well, and squeeze cement into formation until desired pressure is achieved. Cut well off 3' below ground level, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE  
Date/Time Plugging Completed: 01/05/2012 2:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1" pipe to TD, circulated portland cement to surface, pulled 1" pipe out, topped off well, hooked on to 2-1/2" casing, squeezed cement into well, shut in at 500 psi. Contractor indicated that they used 69 sacks cement to plug well.

Perfs:

Top	Bot	Thru	Comments
823	843		SQUIRREL

RECEIVED

FEB 13 2012

KCC Chanute Dist. #3

JA

Remarks:

Plugged through: TBG

District: 03

Signed

*John Almond*  
(TECHNICIAN)

cc to WC 2/17/12

RECEIVED  
Form CP-2/3  
FEB 16 2012  
2/24/12  
KCC WICHITA