

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20376-00-00
Spot: SENESENE Sec/Twnshp/Rge: 34-21S-19E
3499 feet from S Section Line, 84 feet from E Section Line
Lease Name: SUMMERS Well #: 1-75-P
County: ANDERSON Total Vertical Depth: 852 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	20		
PROD	2.5	821		30 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/28/2011 12:00 PM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string, tie onto well and squeeze cement until desired pressure is achieved. Cut off pipe 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE
Date/Time Plugging Completed: 11/29/2011 2:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1" pipe and packer to 750', squeezed cement into well, shut in at 500 psi. Let well set for a day and pulled 1" and packer out, ran 1" down backside of casing to 500', circulated cement to surface, pulled 1" out, ran 1" down inside casing to 800', circulated cement to surface, pulled 1" out, topped off well. Contractor indicated that they used 99 sacks cement to plug well.

Perfs:

Top	Bot	Thru	Comments
821	847		SQUIRREL

RECEIVED

FEB 13 2012

JA

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)

RECEIVED Form CP-2/3

FEB 16 2012 2/26/12

KCC WICHITA