

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-22701-00-01  
Spot: W2SEW Sec/Twnshp/Rge: 35-21S-19E  
3300 feet from S Section Line, 3635 feet from E Section Line  
Lease Name: SUMMERS Well #: 1 P 85  
County: ANDERSON Total Vertical Depth: 838 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.25	21		
PROD	2.875	838		

Well Type: EOR UIC Docket No: E06421.7 Date/Time to Plug: 01/06/2012 12:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: RUN WORK STRING TO BOTTOM, CEMENT TO SURFACE. PULL WORK STRING, TIE ONTO WELL AND SQUEEZE CEMENT UNTIL DESIRED PRESSURE IS ACHIEVED. CUT PIPE OFF 3' BELOW SURFACE, CAP, AND BACKFILL.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE  
Date/Time Plugging Completed: 01/06/2012 12:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1" pipe to TD, circulated portland cement to surface, pulled 1" out, topped off well, hooked on to 2-1/2" squeezed cement into casing, shut in at 600 psi. Contractor indicated that they used 75 sacks cement to plug well.

Perfs:

Top	Bot	Thru	Comments
813	829		SQUIRREL

RECEIVED

FEB 13 2012 JA

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

  
(TECHNICIAN)

cc to UIC 2/17/12

RECEIVED Form CP-2/3  
FEB 16 2012  
KCC WICHITA 2/21/12