

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-22082-00-02
Spot: SWNESWSW Sec/Twnshp/Rge: 14-21S-19E
860 feet from S Section Line, 4420 feet from E Section Line
Lease Name: BENJAMIN / KNIGHT Well #: 2 INJ
County: ANDERSON Total Vertical Depth: 878 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.625	50		25 SX
PROD	2.875	868		145 SX

Well Type: EOR UIC Docket No: E29001.1 Date/Time to Plug: 01/04/2012 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface, and squeeze cement until desired pressure is achieved. Cut off pipe 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 01/04/2012 12:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1" pipe to TD, circulated portland cement to surface, pulled 1" out, topped off well, hooked up to 2-1/2" and squeezed cement into casing, shut in at 500 psi. Contractor indicated that they used 45 sacks to plug well.

Perfs:

Top	Bot	Thru	Comments
794	830		SQUIRREL

RECEIVED

FEB 13 2012

KCC Chanute Dist. #3

JA

Remarks:

Plugged through: TBG

District: 03

Signed

John Almond
(TECHNICIAN)

cc to UIC 2/17/12

RECEIVED

FEB 16 2012

KCC WICHITA

Form CP-2/3

2/21/12