

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-21658-00-00  
Spot: NESENWSW Sec/Twnshp/Rge: 3-22S-19E  
1870 feet from S Section Line, 4040 feet from E Section Line  
Lease Name: BUCHANAN Well #: 5181  
County: ANDERSON Total Vertical Depth: 843 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.25	50		5 SX
PROD	2	843		113 SX

Well Type: EOR UIC Docket No: E09179.7 Date/Time to Plug: 01/27/2012 12:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Wash work string to bottom, cement to surface. Pull work string out, tie on to well, and squeeze cement into formation until desired pressure is achieved. Cut well off 3' below ground level, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE  
Date/Time Plugging Completed: 01/27/2012 2:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1" to TD, circulated portland cement to surface, pulled 1" out and topped off well, hooked on to 2" and squeezed cement into well, shut in at 500 psi. Contractor indicated that they used 77 sacks of cement to plug well.

Perfs:

RECEIVED  
FEB 13 2012 JA  
KCC Chanute Dist #3

Remarks:

Plugged through: TBG

District: 03

Signed

John Almond  
(TECHNICIAN)

RECEIVED

FEB 16 2012 CP-2/3

KCC WICHITA

cc to UIC 2/17/12

2/21/12