

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-21659-00-00
Spot: SENWSW Sec/Twnshp/Rge: 3-22S-19E
1485 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BUCHANAN Well #: 6181
County: ANDERSON Total Vertical Depth: 860 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.25	21		
PROD 2		858		

Well Type: EOR UIC Docket No: E09179.6 Date/Time to Plug: 01/27/2012 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface, and squeeze cement until desired pressure is achieved. Cut off pipe 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 01/27/2012 12:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1" pipe to TD, circulated portland cement to surface, pulled 1" out, topped off well, hooked on to 2" and squeezed cement into well, shut in at 500 psi. contractor indicated he used 32 sacks cement to plug well.

Perfs:

Top	Bot	Thru	Comments
830	845		

RECEIVED

FEB 13 2012 JA

KCC Chanute Dist #3

Remarks:

Plugged through: TBG

District: 03

Signed

John Almond
(TECHNICIAN)

RECEIVED

Form CP-2/3

FEB 16 2012

KCC WICHITA

cc to uic 2/17/12

2/21/12