

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-21660-00-00
Spot: SENWNWSW Sec/Twnshp/Rge: 3-22S-19E
2075 feet from S Section Line, 4860 feet from E Section Line
Lease Name: BUCHANAN Well #: 7181
County: ANDERSON Total Vertical Depth: 849 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.5	22		5 SX
PROD 2		849		113 SX

Well Type: EOR UIC Docket No: E09179.5 Date/Time to Plug: 01/26/2012 12:00 PM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface, and squeeze cement until desired pressure is achieved. Cut off pipe 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 01/26/2012 2:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1" pipe to TD, circulated portland cement to surface, pulled 1" out, topped off well, hooked on to 2" and squeezed cement into well, shut in at 500 psi. Contractor indicated that they used 30 sacks cement to plug well.

Perfs:

RECEIVED
FEB 13 2012 JA
KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)

cc to UIC 2/17/12

RECEIVED Form CP-2/3
FEB 16 2012
KCC WICHITA