

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20013-00-00
Spot: SENW Sec/Twnshp/Rge: 35-21S-19E
3051 feet from S Section Line, 2855 feet from E Section Line
Lease Name: CAMERON Well #: 3
County: ANDERSON Total Vertical Depth: 848 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10	25		
PROD	2	848		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/11/2012 12:00 PM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: RUN WORK STRING TO BOTTOM, CEMENT TO SURFACE. PULL WORK STRING, TIE ONTO WELL AND SQUEEZE CEMENT UNTI DESIRED PRESSURE IS ACHIEVED. CUT OFF PIPE 3' BELOW SURFACE, CAP, AND BACKFILL.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 01/13/2012 12:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 2" packer on 1" pipe down to 750', squeezed cement down through the packer, pulled packer and pipe out, ran 1" pipe back inside to 800', circulated portland cement to surface. Ran 1' pipe down backside of 2" pipe to 500', circulated portland cement to surface, pulled 1" pipe out, topped off well. Contractor indicated he used 190 sacks cement to plug this well.

Perfs:

Top	Bot	Thru	Comments
805	828		SQUIRREL

RECEIVED

FEB 13 2012

JA


KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)

RECEIVED

FEB 16 2012

Form CP-2/3

KCC WICHITA

2/21/12