

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-207-21608-00-00
Spot: NWNWNWNE Sec/Twnshp/Rge: 2-24S-16E
5230 feet from S Section Line, 2630 feet from E Section Line
Lease Name: ALEXANDER Well #: W 47
County: WOODSON Total Vertical Depth: 1052 feet

Operator License No.: 32710
Op Name: LAYMON OIL II, LLC
Address: 1998 SQUIRREL RD
NEOSHO FALLS, KS 66758

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	22		6 sx
PROD	2.375	1052		160 SX

Well Type: EOR UIC Docket No: E12706.47 Date/Time to Plug: 01/20/2012 12:00 AM
Plug Co. License No.: 32710 Plug Co. Name: LAYMON OIL II, LLC
Proposal Revd. from: LAYMON OIL II, LLC Company: Phone: (620) 963-2495

Proposed Plugging Method: RUN 1" PLASTIC TUBING INTO 2.875 CASING TO 1052'. PUMP CEMENT INTO TUBING UNTIL CEMENT CIRCULATES TO SURFACE. WILL REMOVE 1" TUBING THEN RUN BACK IN CASING TO APPROX. 550' AND PUMP CEMENT TO SURFACE. WILL REMOVE 1".

Plugging Proposal Received By: WitnessType: NONE
Date/Time Plugging Completed 01/20/2012 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" plastic tubing into 2 7/8" casing to TD. Pumped and circulated cement through the 1" tubing from TD to surface. Pulled 1" tubing up to approximately 550' and circulated cement from there to surface. Pulled the remaining 1" tubing out. Topped well off with cement.

Perfs:

Top	Bot	Thru	Comments
1004	1011		SQUIRREL

RECEIVED

FEB 15 2012 RMB

KCC Chanute Dist #3

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]
(TECHNICIAN)

✓ CC to MIC 2/17/12

RECEIVED

Form CP-2/3

FEB 17 2012

2/21/12

KCC WICHITA