

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-001-21103-00-01
SENENE Sec/Twp/Rge 16 - 26S - 21E
4303 feet from south section line
59 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Daniels MUR06-I (W-38)

Operator: State of Kansas

County Allen

Name & _____

Well Total Depth 740 feet

Address _____

Production Pipe: 2.375 Size Feet 740

AB oil well _____ Gas Well _____ SWD Well/ Input Well EOB-XXXX D & A _____

Surface Casing: 6.25 Size Feet _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road Chanute, KS 66720

Company to plug at: Hour: _____ Day: 19 Month: 3 2010

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-9212

Were: Clean out and prepare well for plugging and circulate cement to surface.

Plugging Proposal Received by: Ryan M. Duling

TECHNICIAN

Plugging attended by Agent: All XXXX Part _____ None _____

Operations Completed: Hour: _____ Day: 19 Month: 3 2010

Actual Plugging Report: Dug down beside the 6.25" surface casing. Torched hole in 6.25" casing

to verify 2.375" casing was cemented inside the 6.25" casing. Ran 1" pipe down the inside of the 2.375"

casing to 740'. Circulated cement through the 1" pipe inside the 2.375" casing from 740' to surface. Pulled

375' of 1" pipe. Circulated cement through the 1" pipe inside the 2.375" casing from 350' to surface. Pulled

the rest of the 1" pipe. Topped the 2.375" casing off with cement. Squeezed well to 500 psi. A total of 30

sacks of portland cement was used to plug this well. The well was cut off below surface and the site was

restored.

Remarks: Contract #12391 Control #20100001-006 37.78778 -095.101660 NAD 83

(If additional description is necessary, use BACK of this form.)

GPS'd 4-14-09 By FG.

I did observe this plugging.

Signed:

[Signature]
TECHNICIAN

RECEIVED
JAN 24 2011

KCC WICHITA