

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER .15-001-21186-00-01
SESWNE Sec/Twp/Rge 16-26S-21E
3143 feet from south section line
1761 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Daniels MUR62-I (W-16)

Operator: State of Kansas

County Allen

Name & _____

Well Total Depth 705 feet

Address _____

Production Pipe: 2 Size Feet 705

AB oil well _____ Gas Well _____ SWD Well/ Input Well EDP XXXX D & A _____

Surface Casing: 6.25 Size Feet _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road Chanute, KS 66720

Company to plug at: Hour: _____ Day: 16 Month: 2 2010

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-9212

Were: Clean out and prepare well for plugging and circulate cement to surface.

Plugging Proposal Received by: Ryan M. Duling

Plugging attended by Agent: All _____ Part _____
TECHNICIAN
None XXXX

Operations Completed: Hour: _____ Day: 16 Month: 2 2010

Actual Plugging Report: Dug down beside the 6.25" surface casing with a backhoe. Torched hole in the 6.25" casing to verify 2" casing is cemented inside the 6.25" surface casing. Ran 1" pipe inside the 2" casing to 705'. Circulated cement through the 1" pipe inside the 2" casing from 705' to surface. Pulled 350' of 1" pipe. Circulated cement through the 1" pipe down the inside of the 2" casing from 350' to surface. Pulled the remaining 1" pipe. Topped casing off with cement. Squeezed casing to 450 psi. A total of 30 sacks of portland cement was used to plug this well. The well was cut off below surface and the site was restored.

Remarks: Contract #12391 Control #20100001-062 37.78463-095.11248 NAD 83
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed: Ryan M. Duling
TECHNICIAN

RECEIVED
JAN 24 2011
KCC WICHITA
CPSD 4-15-09 BY F.G.