

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23588-00-00
Spot: SENWSESE Sec/Twnshp/Rge: 25-16S-22W
979 feet from S Section Line, 986 feet from E Section Line
Lease Name: KRESSIN Well #: 2
County: NESS Total Vertical Depth: 4360 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3850		
SURF	8.625	212		WITH 130 SX CMT
DVT		1666		CEMENTED WITH 250 SX CMT
PROD	4.5	4300	0	WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/24/2012 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: THAD STARR Company: AMERICAN ENERGIES Phone: (620) 793-2146

Proposed
Plugging
Method:

TO RUN TBG AS DEEP AS POSSIBLE & CIRCULATE HOLE FULL OF CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/24/2012 11:55 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

COMPANY CALLED THE DISTRICT AFTER ATTEMPTING TO GET TBG BACK DOWN THE HOLE BUT DRILLED OUT CASING AT 270'. GETTING FORMATION BACK IN CIRCULATION A SUBMERSIBLE PUMP WAS LOST IN THE HOLE & PUSHED DOWN TO 1167' 10 YEARS AGO. ANOTHER SUBMERSIBLE PUMP WAS LOST IN THE HOLE & PUSHED DOWN THE HOLE TO 716' & COMPANY LOST AN UNKNOWN AMOUNT OF DRILL COLLARS ON TOP OF IT. THE TOP JOINT OF 4 1/2" CASING IS CORRODED INTO BELOW THE BRADEN HEAD. RAN 1" TBG INSIDE THE 8 5/8" X 4 1/2" ANNULUS TAGGING CMT AT 50'. RAN 1" TBG TO 250' INSIDE THE 4 1/2" & COULDN'T GET ANY FURTHER. PULLED 1" OUT. RAN 2 3/8" TBG TO 248'. PUMPED 50 SX CMT CIRCULATING CMT TO SURFACE UP 8 5/8" & 4 1/2". SHUT IN CASING'S & PUMPED 350 SX CMT DOWN HOLE AT 250 PSIG. SHUT IN PRESSURE WAS LESS THAN 50 PSIG BUT WOULDN'T STOP FLOWING BACK. WELL FLOWED BACK APPROXIMATELY 10 SX CMT. PULLED TBG. 4 1/2" CASING NIPPLE FELL OFF & WELL FLOWED BACK ANOTHER 90 SX APPROXIMATELY. 1/25/12: CHECKED TOP PLUG. WELL TOOK APPROXIMATELY 10 SX BACK DOWN THE WELL. TOP OF CMT IS 10'.

Perfs:

Top	Bot	Thru	Comments
1306	1350		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED
FEB - 3 2012
KCC DODGE CITY

RECEIVED
FEB 13 2012
KCC WICHITA

Form CR-2/3

✓ 2/20/12