

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-23346-00-02  
Spot: SENE Sec/Twnshp/Rge: 25-16S-22W  
3221 feet from S Section Line, 731 feet from E Section Line  
Lease Name: LINDEN Well #: 3  
County: NESS Total Vertical Depth: 4472 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1750		
SURF	8.625	257		WITH 170 SX CMT
DVT		1676		CEMENTED WITH 400 SX CMT
PROD	5.5	4484	0	WITH 525 SX CMT

Well Type: WSW UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/25/2012 2:30 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: THAD STARR Company: AMERICAN ENERGIES Phone: (316) 263-5785

Proposed Plugging Method: TO RUN TBG AS DEEP AS POSSIBLE & CIRCULATE HOLE FULL OF CMT. PRESSURE TEST 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/25/2012 4:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

RAN TBG TO 1215'. PUMPED 70 SX CMT FOLLOWED BY 80 SX CMT WITH 300#HULLS MIXED IN. CIRCULATED CMT TO SURFACE. PULLED TBG OUT OF HOLE. TOPPED OFF 5 1/2" CASING WITH 10 SX CMT. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH 2 SX CMT.

Perfs:

Top	Bot	Thru	Comments
1748	1750		ANHYDRITE
1240	1280		CEDAR HILL

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR\*\* USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

*Richard W. Lacey*

(TECHNICIAN)

RECEIVED  
FEB - 3 2012  
KCC DODGE CITY

RECEIVED  
FEB 13 2012  
KCC WICHITA

Form 10-200

2/20/12